



Solifier LLC, 5900
Balcones Drive # 17035,
Austin Texas USA 78731

SR #	CSI SECT	DESCRIPTION	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
DIV. 06 WOOD, PLASTIC AND COMPOSITES									\$ -
Wooden Posts									
1		9'-11 1/4" Long, 3 1/2"x 5 1/4" PSL Post	1	0%	1	EA		\$ -	
2		9'-11 1/4" Long, 5 1/4"x 5 1/4" PSL Posts	4	0%	4	EA		\$ -	
3		9'-11 1/4" Long, 6"x6" Pressure Treated Posts	4	0%	4	EA		\$ -	
4		9'-11 1/4" Long, 3 1/2"x 5 1/4" PSL Posts	1	0%	1	EA		\$ -	
5		9'-11 1/4" Long, 5 1/4"x 5 1/4" PSL Posts	4	0%	4	EA		\$ -	
6		06p: 9'-11 1/4" Long, 3 1/2"x3 1/2" PSL Posts	3	0%	3	EA		\$ -	
Structural Lumber									
7		10'-0" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	3	0%	3	EA		\$ -	
8		11'-10" Long, 2x10 SPF #2 Beams	4	0%	4	EA		\$ -	
9		12'-6" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA		\$ -	
10		12'-8" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	6	0%	6	EA		\$ -	
11		13'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	3	0%	3	EA		\$ -	
12		13'-3" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	3	0%	3	EA		\$ -	
13		14'-8" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA		\$ -	
14		2"x6" Roof Over Hang Lumbers	17	0%	17	EA		\$ -	
15		2'-0" Long, Roof Trusses	5	0%	5	EA		\$ -	
16		21'-0" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA		\$ -	
17		21'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Beams	2	0%	2	EA		\$ -	

18	21'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber	2	0%	2	EA	\$	-
19	29'-0" Long, 2"x8" Bolted Ledger	1	0%	1	EA	\$	-
20	29'-8" Long, 4"x8" Western Red Cedar Beams	1	0%	1	EA	\$	-
21	3'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber	6	0%	6	EA	\$	-
22	40'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA	\$	-
23	4'-2" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Beams	2	0%	2	EA	\$	-
24	4'-6" Long, 2x10 SPF #2 Beams	4	0%	4	EA	\$	-
25	257'-4" Long, 5/4x8 Trim Board	1	0%	1	EA	\$	-
26	6'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA	\$	-
27	7'-6" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams	2	0%	2	EA	\$	-
Headers							
28	1'-9" Long, 2"x8" SPF Headers	8	0%	8	EA	\$	-
29	2'-0" Long, 2"x8" SPF Headers	4	0%	4	EA	\$	-
30	2'-10" Long, 2"x7" SPF Headers	4	0%	4	EA	\$	-
31	2'-10" Long, 2"x8" SPF Headers	4	0%	4	EA	\$	-
32	2'-11" Long, 2"x8" SPF Headers	6	0%	6	EA	\$	-
33	2'-3" Long, 2"x8" SPF Headers	2	0%	2	EA	\$	-
34	2'-6" Long, 2"x8" SPF Headers	12	0%	12	EA	\$	-
35	2'-7" Long, 2"x8" SPF Headers	8	0%	8	EA	\$	-
36	2'-8" Long, 2"x8" SPF Headers	4	0%	4	EA	\$	-
37	2'-9" Long, 2"x8" SPF Headers	6	0%	6	EA	\$	-
38	3'-10" Long, 2"x8" SPF Headers	2	0%	2	EA	\$	-
39	3'-3" Long, 2"x8" SPF Headers	8	0%	8	EA	\$	-
40	4'-3" Long, 2"x8" SPF Headers	8	0%	8	EA	\$	-
41	4'-8" Long, 2"x7" SPF Headers	2	0%	2	EA	\$	-
42	5'-0" Long, 2"x7" SPF Headers	2	0%	2	EA	\$	-
43	5'-0" Long, 2"x8" SPF Headers	2	0%	2	EA	\$	-
44	5'-3" Long, 2"x7" SPF Headers	2	0%	2	EA	\$	-
45	6'-4" Long, 2"x8" SPF Headers	2	0%	2	EA	\$	-
46	9'-10" Long, 3 1/4" x9 1/4" Laminated Headers	2	0%	2	EA	\$	-
Joists, Rafters and Trusses							

47	11'-4" Long, 11 7/8" TJI Wood Joists	2	0%	2	EA	\$	-
48	13'-0" Long Girder Trusses	2	0%	2	EA	\$	-
49	13'-0" Long, Roof Trusses	22	0%	22	EA	\$	-
50	13'-6" Long, 2"x8" Rafters	6	0%	6	EA	\$	-
51	14'-0" Long, Roof Trusses	23	0%	23	EA	\$	-
52	14'-8" Long, Roof Trusses	22	0%	22	EA	\$	-
53	15'-10" Long, 11 7/8" TJI Wood Joists	10	0%	10	EA	\$	-
54	17'-0" Long, Roof Trusses	16	0%	16	EA	\$	-
55	19'-10" Long, 11 7/8" TJI Wood Joists	41	0%	41	EA	\$	-
56	21'-5" Long, 11 7/8" TJI Wood Joists	26	0%	26	EA	\$	-
57	24'-11" Long Girder Truss	1	0%	1	EA	\$	-
58	26'-0" Long, Roof Trusses	11	0%	11	EA	\$	-
59	26'-9" Long, Roof Trusses	4	0%	4	EA	\$	-
60	3'-10" Long, 11 7/8" TJI Wood Joists	1	0%	1	EA	\$	-
61	40'-10" Long Girder Trusses	2	0%	2	EA	\$	-
62	41'-3" Long, Roof Trusses	8	0%	8	EA	\$	-
63	41'-3" Long Girder Truss	1	0%	1	EA	\$	-
64	4'-4" Long, Roof Trusses	9	0%	9	EA	\$	-
65	8'-6" Long, 9 1/2" TJI Joists	3	0%	3	EA	\$	-
66	7'-2" Long Girder Trusses	2	0%	2	EA	\$	-
67	9'-6" Long Girder Truss	1	0%	1	EA	\$	-
Wall Studs							
68	2"x4" Wood Studs	2,829	10%	3,112	LF	\$	-
69	2"x6" Wood Studs	3,268	10%	3,595	LF	\$	-
Top and Bottom Plates							
70	2"x4" Top Plates	439	10%	483	LF	\$	-
71	2"x4" Bottom Plates	439	10%	483	LF	\$	-
72	2"x6" Top Plates	497	10%	547	LF	\$	-
73	2"x6" Bottom Plates	209	10%	230	LF	\$	-
74	2"x6" Mudsill	288	10%	316	LF	\$	-
Plywood Sheathing							
75	3/4" Plywood Floor Sheathing (132 Sheets of 4'x8')	3,842	10%	4,226	SF	\$	-
76	1/2" Plywood Roof Sheathing (133 Sheets of 4'x8')	3,864	10%	4,250	SF	\$	-
77	1/2" Plywood Wall Sheathing (156 Sheets of 4'x8')	4,524	10%	4,976	SF	\$	-

SUB TOTAL			\$ -	\$ -
OVERHEAD & PROFIT (25%)		25%	\$ -	\$ -
TOTAL BID			\$ -	\$ -